could satisfy the need of the irrigators. Moduling of outlets can be extended to the moduling of heads of minors by constructing meter flumes. The experience at Dhaular distributary system at Darshan head, Budduana head and Lakhbadar head shows that excess supplies can be distributed to the offtakes in a controlled manner to keep the variation factor within permissible limits. It is, however, essential to have meters at the head of a channel and at suitable intervals down the channel to achieve operational control of the system.